



SECTION B: PRELIMINARIES

Definition and interpretation (B1)

A Definition and interpretation (B1.1 - B1.6.5)

F:.....V:.....T:.....

Item **Not Priced**

Documents (B2)

B Checking of documents (B2.1)

F:.....V:.....T:.....

Item **Not Priced**

C ??These bills of quantities contain pages and annexures as indexed on the flyleaf??

??The items in these bills of quantities are to be read and priced in conjunction with and the descriptions regarded as amplified by the Model Preambles for Trades as recommended and published by the Association of South African Quantity Surveyors, 1997 edition, and no claim arising from brevity of description of items fully described in the said Model Preambles for Trades will be entertained ??

Item **Not Priced**

D Provisional bills of quantities (B2.2)

F:.....V:.....T:.....

N/A

E ?? These bills of quantities are in Multiple Procurement format i.e. the "Wet Trades" - earthworks, concrete, formwork and reinforcement, precast concrete, masonry, waterproofing and sub-surface drainage are fully measured and the subsequent trades are budgetary allowances??

F:.....V:.....T:.....

Item **Not Priced**

F Availability of construction documentation (B2.3)

F:.....V:.....T:.....

Item **Not Priced**

G ??The budgetary allowances allocated for subsequent trades included in this document will be separately procured, based on multiple procurement of ?? nominated/selected ?? subcontractors during the construction period??

F:.....V:.....T:.....

Item **Not Priced**

H Interests of agents (B2.4)

F:.....V:.....T:.....

Item **Not Priced**

I Priced documents (B2.5)

F:.....V:.....T:.....

Item **Not Priced**

Carried to Collection

R **Not Priced**

Bill No. 1
PRELIMINARIES



Brought Forward

R

Excavation in earth not exceeding 2m deep and spoil adjacent to excavation for later re-use

2	Trenches	A: 171	B: 96	C: 82	D: 13	E: 47	F: 30	G: 0	J: 48		
		K: 11	L: 77	M: 94	N: 55	O: 46	P: 12			m3	781
3	Column bases	A: 0	B: 0	C: 0	D: 0	E: 0	F: 0	G: 0	J: 0		
		K: 0	L: 63	M: 0	N: 0	O: 0	P: 0			m3	63
4	Holes	A: 9	B: 5	C: 4	D: 2	E: 0	F: 1	G: 0	J: 8		
		K: 0	L: 0	M: 78	N: 51	O: 0	P: 1			m3	158
5	Surface bed and thickening under surface beds etc	A: 0	B: 0	C: 0	D: 0	E: 3	F: 0	G: 0	J: 5		
		K: 0	L: 0	M: 0	N: 0	O: 1	P: 0			m3	9
<u>Extra over trench and hole excavations in earth for excavation in</u>											
6	Dumprock	A: 180	B: 101	C: 86	D: 15	E: 50	F: 31	G: 0	J: 60		
		K: 11	L: 140	M: 173	N: 106	O: 47	P: 12			m3	1,012
<u>Extra over all excavations for carting away</u>											
7	Surplus material from excavations and/or stock piles on site to a dumping site within the 3Km freehaul distance	A: 117	B: 66	C: 0	D: 9	E: 0	F: 20	G: 0	J: 4		
		K: 6	L: 87	M: 0	N: 0	O: 9	P: 8			m3	326
<u>Risk of collapse of excavations</u>											
8	Sides of trench and hole excavations not exceeding 1,5m deep	A: 0	B: 0	C: 265	D: 49	E: 151	F: 0	G: 0	J: 168		
		K: 0	L: 0	M: 0	N: 0	O: 154	P: 0			m2	786
9	Sides of excavations not exceeding 1,5m deep	A: 0	B: 0	C: 0	D: 0	E: 0	F: 0	G: 0	J: 0		
		K: 35	L: 434	M: 395	N: 291	O: 0	P: 0			m2	1,156
10	Sides of bulk excavations not exceeding 1,5m deep	A: 555	B: 312	C: 0	D: 0	E: 0	F: 97	G: 0	J: 0		
		K: 0	L: 0	M: 0	N: 0	O: 0	P: 37			m2	1,002

Bill No. 4
EARTHWORKS
Test Project



Demo Project WIDE BoQ NO Amounts

	Brought Forward						R	39,164.32
	<u>Excavation in earth not exceeding 2m deep and spoil adjacent to excavation for later re-use</u>							
2	Trenches							
	A: 171	B: 96	C: 82	D: 13				
	E: 47	F: 30	G: 0	J: 48				
	K: 11	L: 77	M: 94	N: 55				
	O: 46	P: 12			781	m3	38.20	29,834.20
3	Column bases							
	A: 0	B: 0	C: 0	D: 0				
	E: 0	F: 0	G: 0	J: 0				
	K: 0	L: 63	M: 0	N: 0				
	O: 0	P: 0			63	m3	45.25	2,850.75
4	Holes							
	A: 9	B: 5	C: 4	D: 2				
	E: 0	F: 1	G: 0	J: 8				
	K: 0	L: 0	M: 78	N: 51				
	O: 0	P: 1			158	m3	51.24	8,095.92
5	Surface bed and thickening under surface beds etc							
	A: 0	B: 0	C: 0	D: 0				
	E: 3	F: 0	G: 0	J: 5				
	K: 0	L: 0	M: 0	N: 0				
	O: 1	P: 0			9	m3	38.20	343.80
	<u>Extra over trench and hole excavations in earth for excavation in</u>							
6	Dumprock							
	A: 180	B: 101	C: 86	D: 15				
	E: 50	F: 31	G: 0	J: 60				
	K: 11	L: 140	M: 173	N: 106				
	O: 47	P: 12			1,012	m3		Not in BOQ
	<u>Extra over all excavations for carting away</u>							
7	Surplus material from excavations and/or stock piles on site to a dumping site within the 3Km freehaul distance							
	A: 117	B: 66	C: 0	D: 9				
	E: 0	F: 20	G: 0	J: 4				
	K: 6	L: 87	M: 0	N: 0				
	O: 9	P: 8			326	m3	28.80	9,388.80
	Carried Forward						R	89,677.79
	Bill No. 4 EARTHWORKS Test Project							